



**WATER AND SEWER DIVISIONS  
DEPARTMENT OF PUBLIC UTILITIES**

Town of Wallingford  
377 South Cherry Street  
Wallingford, Connecticut 06492  
Telephone: 203-949-2672

**North Main Street Water Main Replacement Project**

The Wallingford Water Division is currently replacing the existing parallel cast iron water mains along North Main Street between Christian Street and Cedar Lane. The existing 4-, 6-, and 8-inch water mains were constructed between 1883 and 1921. The Water Division's water main asset management program identified these water mains for replacement due to their pipe age, pipe material, bedding conditions, break history and headloss per length.

A new, single 8-inch or 12-inch (depending on the location) ductile iron water main will be installed along North Main Street from Christian Street to Cedar Lane. Following installation of the new ductile iron water main, new water services will be installed between the pipe below the road and the water service curb box located on each property within the construction limits. Additionally, the new water main will be connected to the existing water mains that intersect North Main Street.

This work is scheduled to be completed by Friday, October 27, 2017. Please note that final pavement restoration will occur in spring 2018 following the winter season.

**During construction, we ask that you allow additional time to travel along North Main Street, including to and from the Moses Y. Beach Elementary School and the Town Hall area. We also request that you be careful of your speed, and watch for construction workers, equipment and materials working in or next to the roadway.**

Should you have any questions or require additional information please feel free to contact the Water Division project manager, Seth Lentz, P.E., at 203-949-2672. Thank you.